

GOVERNMENT CENTER PARKING LOT

210 E WASHINGTON STREET

GOVERNMENT CENTER PARKING LOT NOTES

1. PATCHES SHOWN ARE FOR REFERENCE ONLY. EXACT SIZE AND LOCATION TO BE DETERMINED BY THE ENGINEER AFTER SURFACE REMOVAL.
2. ALL EXISTING HMA SHALL BE REOMVED FROM THE GUTTER PANS. THIS QUANTITY IS INCLUDED IN PLAN QUANTITIES. SEE SPECIAL PROVISIONS.
3. AFTER HMA SURFACE REOMOVATION OPERATIONS ARE COMPLETE AND AFTER THE BITUMINOUS MATERIALS TACK COAT HAS BEEN APPLIED, LOW AREAS IN REMAINING PAVEMENT SURFACE WILL BE FILLED BY HAND OR WITH THE PAVER AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID IN ACCORDANCE WITH ARTICLE 109.04.
4. ALL STRIPING AND PAINTING TO BE DONE BY THE McLEAN COUNTY HIGHWAY DEPARTMENT AFTER CONTRACT WORK.



GOVERNMENT CENTER PARKING LOT QUANTITIES			
CODE NUMBER	ITEM	UNIT	QUANTITY
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL 9.5, MIX "C", N50	TON	475
40700100	BITUMINOUS MATERIALS (TACK COAT)	POUND	875
*44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3890
*44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	175

* = SPECIAL PROVISION

APPROXIMATE PATCHING AREAS	
PATCH NUMBER	SQ YDS
P1	18.9
P2	24.1
P3	80
P4	30.6
P5	20
P6	31
TOTAL	204.6 SQ YDS
PLAN ROUND-UP	205 SQ YDS



MODEL: Default
 FILE NAME: X:\County\Parking_Lots\2022_Government_Center_Parking_Lot\Gov_Center_Parking_Lot.dgn

USER NAME = eric.geurts	DESIGNED -	REVISED -
PLOT SCALE = 40.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 2/18/2022	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GOVERNMENT CENTER PARKING LOT
201 EAST WASHINGTON ST

SCALE: 1" = 40' SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	21-00600-00-R5	McLEAN		
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				

EAST EMPIRE ST

METCOM PARKING LOT

2411 EAST EMPIRE ST



METCOM PARKING LOT NOTES

1. CLASS D PATCHING QUANTITY INCLUDED AS A CONTINGENCY ITEM AND WILL ONLY BE USED IF REQUIRED AS DETERMINED BY THE ENGINEER AFTER SURFACE REMOVAL.
2. ALL EXISTING HMA SHALL BE REMOVED FROM THE GUTTER PANS. THIS QUANTITY IS INCLUDED IN PLAN QUANTITIES. SEE SPECIAL PROVISIONS.
3. AFTER HMA SURFACE REOMOVAL OPERATIONS ARE COMPLETE AND AFTER THE BITUMINOUS MATERIALS TACK COAT HAS BEEN APPLIED. LOW AREAS IN REMAINING PAVEMENT SURFACE WILL BE FILLED BY HAND OR WITH THE PAVER AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID IN ACCORDANCE WITH ARTICLE 109.04.
4. EXISITNG HMA THICKNESSES VARY THROUGH OUT THE PARKING AREA. IT IS ANTICIAPTED THAT HMA SURFACE REMOVAL OPERATIONS WILL EXPOSE PORTIONS OF THE AGGREGATE BASE. THE PAY ITEM "SHAPE AND COMPACT AGGREGATE BASE COURSE = 500 SQ YDS", IS AN ESTIMATED QUANTITY. THIS ITEM WILL BE MEASURED IN PLACE AND PAID AT THE CONTRACT UNIT PRICE PER SQ YD, FOR "SHAPE AND COMPACT AGGREGATE BASE COURSE"



METCOM PARKING LOT QUANTITIES			
CODE NUMBER	ITEM	UNIT	QUANTITY
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	180
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL 9.5, MIX "C", N50	TON	140
*40700100	BITUMINOUS MATERIALS (TACK COAT)	POUND	860
*44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	1270
*44201696	CLASS D PATCHES, TYPE IV 4 INCH	SQ YD	50
*LR355215	BITUMINOUS MATERIALS (BASE COURSE)	GALLON	175
*	SHAPE AND COMPACT AGGREGATE BASE COURSE	SQ YD	500

* = SPECIAL PROVISION

MODEL: Default
FILE NAME: X:\County\Parireng_Lots\2022_Metcom_Parking_Lot\Metcom_Parking_Lot.dgn

USER NAME = eric.geurts	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40,0000' / in.	CHECKED -	REVISED -
PLOT DATE = 3/21/2022	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**METCOM PARKING LOT
2411 EAST EMPIRE ST**

SCALE: 1" = 40' SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	21-00600-00-R5	McLEAN		
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				